7

1026

V I

Office of Light-House Engineer,

FIRST AND SECOND DISTRICTS,

Boston, Mass., February 8, 1886

To the Chairman.
Light-House Board.
Washington, D.C.

Sir:

Pursuant to instructions conveyed in the letter from the Board of the 11th of January 1886, I have the honor to report that as Robinsons Point, Isle au Haut, Maine is rocky and wooded the establishment of a light-house there is entirely practicable, and to submit the following estimate therefor.

For a brick tower 20 feet high with 4th order lantern, deck and stairs	3000.00
For a frame dwelling with brick Cistern for one keeper	3.500.00
For a boat house and slip	700.00
For a fuel house	300.00
Carried forward	7.500.00

1028

Office of Light-House Engineer,

FIRST AND SECOND DISTRICTS.

Boston, Mass., , 188

Brought forward	7,500.00
For 1000 lb fog-bell with Stevens' Machine, bell house and tower	1,000.00
For contingencies and purchase of site — say.	2,500.00
Total	$11,000.00

An iron tower lined with brick is estimated to cost $1000. more than the above.

It will be observed that the foregoing estimates do not embrace the cost of the lens.

Very Respectfully
Your Obt Servt.

W. S. Stanton
Major of Engineers
Engrs 1st & 2d L.H. Dists