
Estimate of expense of a land mark on Dowditz
ledge in Salem Harbour

The rocks that now lay promiscuously scattered on the
mains of the old pier are to be removed and the
undation, for the flat stone which is to receive the
ak Spar, is to be made level. Then the flat stone
hich is to be 10 feet over of an octagonal shape and
o feet thick in the centre is to be placed thereon
nd bolted with copper into the work of the old
ier with bolts of 1½ inch. The white oak Spar to
e squared and 20 to 25 feet in length and to be mortised
nto the stone and secured either by wedges or lead
On the top of the Spar is to be placed a frame work
n order to make the mark conspicuous — This to be
ompleted in 30 days from the time of agreement

Memo — After the foundation is cleared the surface of the old
ier will afford an excellent situation for the flat rock
to be fastened to. The whole being formed in
the first place by split rocks in layers bolted
transversely very near together thus



Price asked $320
perhaps $300.—

For Gen H. A. S. Dearborn
from Gil

Extimate for
fencing the Land
work on Rowdale
as Ledger.—